

RFQ2200221263 Construction of a Tourist Reception Facility in Tuzor, Liberia

LOT2

Company name:

Item	DESCRIPTION	QTY	UNIT	PRICE (USD)	AMOUNT (USD)
A					
	PRELIMINARY				
	PRELIMINARY				
	Site Clearence	1	L/S		\$ -
	Profile and layout	1	L/S		\$ -
	Storage Capacity	4	L/S		\$ -
	Total Preliminary Costs				\$ -
	FOUNDATION WORKS				
	FOUNDATION				
B	Excavate Surface Trench	150	cy		\$ -
	Supply and Install Cement	70	bgs		\$ -
	Fine Aggregates ( Sand )	8	blade		\$ -
	Coarse Aggreates ( ½" Ø Crush Rock )	4	blade		\$ -
	Sand Crete Block wall	2,500	pcs		\$ -
	11mm Ø Steel Rod	28	pcs		\$ -
	6mm Ø Steel Rod	14	pcs		\$ -
	Tie Wire	3	roll		\$ -
	Wawa 1"x12"x14'-0"	20	pcs		\$ -
	Round Poles	30	pcs		\$ -
	Wire Nails	2	cnt		\$ -
	Backfilled	1	cy		\$ -
	Total Foundation Costs				\$ -
	BUILDING STRUCTURE WORKS				
	ROUGH FLOOR				
C	Supply and Install Cement	38	bgs		\$ -
	Fine Aggregates ( Sand )	5	blade		\$ -
	Coarse Aggreates ( ½" Ø Crush Rock )	3	blade		\$ -
	Wawa 1"x12"x14'-0"	5	pcs		\$ -
	Round Poles	15	pcs		\$ -
	Wire Nails	1	ctn		\$ -
	PVC Assories	1	L/S		\$ -
	Sub - Total				\$ -
D	WALLS				
	Supply and Install Cement	85	bgs		\$ -
	Fine Aggregates (Sea Sand)	8	blade		\$ -
	Coarse Aggreates 20-25mm	2	blade		\$ -
	Sandcrete Blocks	3,120	pcs		\$ -
	11mm Steel Rod	30	pcs		\$ -
	8mm Steel Rod	20	pcs		\$ -
	Tie Wire	3	roll		\$ -
	1" x 12" x 14'-0" Wawa	35	pcs		\$ -
	1" x 6" x 14'-0" Wawa	15	pcs		\$ -
	Roundpoles	30	pcs		\$ -
	Assorted Wire Nails	1	cnt		\$ -
	Sub -Total				\$ -
E	ROOFING WORKS				
	Supply and Install Spam Roofing Sheet	5	bdl		\$ -
	Ditto 3" pipe as Ridgeboard, Wallplates and Kingpost	1	L/S		\$ -
	2" diameter pipe as Rafters, Web members, Braces and Formworks	1	L/S		\$ -
	2"x 2"x 14' as Purlins & Formworks	1	L/S		\$ -
	1" x 10" x 14 as Fascia Board	1	pcs		\$ -
	Roofing Felts	10	roll		\$ -
	Aluminium Combing	1	L/S		\$ -
	Carboline	15	gal		\$ -
	Zinc Nails	44	box		\$ -
	Zinc Nails Washers	1	L/S		\$ -
	PVC drine line	2	pcs		\$ -
	Assorted Wire Nails	6	ctn		\$ -
	Wedding rod	1	L/S		\$ -
	Sub - Total				\$ -
F	DOORS				
	Supply and Install Plywood Door 2'-6" x 7'-0" with Hinges, Screws, Lock and 6" Frames and Complete	4	No.		\$ -
	Sub - Total				\$ -
	Total Building structure Cost				\$ -

	FINAL WORKS				
G	PLASTERING				
	Supply and Install Cement	60	bgs		\$ -
	Fine Aggregates (Sea Sand)	8	cy		\$ -
	Accessories	1	L/S		\$ -
	Sub - Total				\$ -
H	PAINTING				
	Oil Paint	2	bucket		\$ -
	Varnish	2	gal		\$ -
	Thinner	2	gal		\$ -
	Painting Accessories	1	l/s		\$ -
	White Wash	2	L/S		\$ -
	Sub - Total				\$ -
I	ELECTRICAL WORKS				
	Supply and Install 12-Breaker Panel Box	1	No.		\$ -
	No. 10 AWG Wire	1	L/S		\$ -
	No. 12 AWG Wire	1	L/S		\$ -
	Junction Cups	1	L/S		\$ -
	Utility Cups	1	L/S		\$ -
	1" Ø Pipes	1	L/S		\$ -
	Single Pole Switch	1	L/S		\$ -
	Receptacles	1	L/S		\$ -
	Sockets	1	L/S		\$ -
	Electrical Tapes	1	L/S		\$ -
	Sub - Total				\$ -
J	PLUMBING WORKS				
	Commode	1	No.		\$ -
	Allow for Septic Tank	1	L/S		\$ -
	Allow for Pipe Running and Connection to Sewer and Septic Tank	1	L/S		\$ -
	Sub - Total				\$ -
K	IRON MONGERY				
	Iron gate 3'-0" x 7'-0"	1	NO		\$ -
	Sub - Total				\$ -
L	TILE WORKS				
	Supply and Install Cement	40	bgs		\$ -
	Fine Aggregates (Sea Sand)	1	L/S		\$ -
	Ceramic Floor Tile (12" x 12")	1	L/S		\$ -
	Ceramic Wall Tiles (8" x 12")	1	L/S		\$ -
	Sub - Total				\$ -
	Total of Final Works				\$ -
	TOTAL CONSTRUCTION COST				\$ -

ITC is exempt of VAT and of any other duties

Prices quoted above should be inclusive of all the costs associated with the provision of the required construction works as detailed in the TOR. ITC will not be responsible for any other costs associated with provision of deliverables, therefore all personnel, travel, allowances, hire, fees and any other related costs shall be all inclusive, i.e. be included in the above rates.

I confirm that the above rates are all inclusive and remain valid for 180 days after tender closure

Signature  
Date

