

Bill of Quantities

	RFQ2200221263 Construction of a multipurpose Surf House at Robertsport, Liberia						
	LOT1		Company name:				
Item	DESCRIPTION	QTY	UNIT	PRICE (USD)	AMOUNT (USD)		
	FOUNDATION WORKS						
A	Mobilization and Site Preparation						
	Allow SUM to mobilize material, labour, equipments to site	1	L/S		\$ -		
	Sub-total to Summary				\$ -		
B	Earth Works						
	Excavate trenches for additional foundation	15.33	CY		\$ -		
	Hardcore/ Sandfill with debris and sand to make up levels	48.13	CY		\$ -		
	Backfill with materials arising from excavation	47.7037	CY		\$ -		
	Sub-total to Summary				\$ -		
C	Concrete Works						
	Mass concrete in strip foundation and ground floor slab:	3.83	CY				
	Ordinary portland cement	40	Bags		\$ -		
	Beach sand	2.19	CY		\$ -		
	Crush rock	2.68333	CY		\$ -		
	Reinforced concrete in columns, beams and lintels:	14.91					
	Ordinary portland cement	15	Bags	\$ -	\$ -		
	Beach sand	7.45	CY	\$ -	\$ -		
	Crush rock	10.44	CY	\$ -	\$ -		
	1/2" Steel rod	19	Pcs		\$ -		
	1/4" Steel rod	12	Pcs		\$ -		
	Tie-wire	50	Kg		\$ -		
	Formwork (fabricating and installation)						
	1"x 12"x 14'-0" Wawa board	40	Pcs		\$ -		
	2"x 2"x 14'-0" Plank	15	Pcs		\$ -		
	Round poles (bush cut)	20	Pcs		\$ -		
	Nylon rope	2	Roll		\$ -		
	4" Wire nail	2	carton		\$ -		
	3" Wire nail	2	carton	\$ -	\$ -		
	2" Wire nail	1	carton	\$ -	\$ -		
	Sub-total to Summary				\$ -		
	Total Foundation Works				\$ -		

Bill of Quantities

Item	DESCRIPTION	QTY	UNIT	PRICE (USD)	AMOUNT (USD)		
	BUILDING STRUCTURE WORKS						
D	Block Work						
	Supply the following materials to construct 6" block walls and plaster both surfaces at designated locations as per extention design						
	6" Hollow sandcrete block	3575	Pcs		\$ -		
	Breeze blocks	8	Pcs		\$ -		
	Ordinar portland cement	120	Bags	\$ -	\$ -		
	Beach sand	24	CY	\$ -	\$ -		
	Sub-total to Summary				\$ -		
E	Roofing						
	supply the following materials to construct roof complete as per design:						
	28 Guage Alloy Roofing sheets	8	Bdl		\$ -		
	Cummings	26	Lft		\$ -		
	Zinc nail with washer	8	Box		\$ -		
	2 x 6 x 14-0" Hardwood plank	80	Pcs		\$ -		
	2 x 4 x 14-0" Hardwood planks	100	Pcs		\$ -		
	2 x 2 x 14-0" Hardwood plank	200	Pcs		\$ -		
	1 x 9 x 14-10 Dressed hardwood fascial board	20	Pcs		\$ -		
	4" Wire nails	15	Carton	\$ -	\$ -		
	3" Wire nails	8	Carton	\$ -	\$ -		
	1 1/2" Wire nails	6	Carton	\$ -	\$ -		
	Sub-total to Summary				\$ -		
F	Ceiling Work						
	Supply the following materials to construct 4'-0"x 4'-0" plywood ceiling with hardwood timber joist:						
	2"x 2"x 14'-0" Hardwood plank	110	Pcs		\$ -		
	Plain middle and corner strips	7	Bdl		\$ -		
	Ceiling tiles (Internal)	40	Pcs		\$ -		
	1/8" thick plywood ceiling tiles (External)	12	Pcs		\$ -		
	4" Wire nail	4	Carton	\$ -	\$ -		
	3" Wire nail	3	Carton	\$ -	\$ -		
	2" Wire nail	3	Carton	\$ -	\$ -		
	1½" Wire nail	2	Carton	\$ -	\$ -		
	1" Wire nail	2	Carton	\$ -	\$ -		
	Sub-total to Summary				\$ -		
G	Doors and Windows						
	Provide and install the following:						
	3'-0"x 7'-0" Door frame	8	Pcs		\$ -		
	2'-8"x 6'-10" Hardwood panel door shutter	2	Pcs		\$ -		
	2'-8"x 6'-10"plywood door shutter	4	Pcs		\$ -		
	Cylinder door lock	6	Set		\$ -		
	4" Brass butt hinges	9	Pair		\$ -		
	Door strips	8	Pcs		\$ -		
	Aluminum framed glass sliding windows with operable aluminum framed fibre screens complete to fit in the following window openings:						
	4'-0"x 5'-0"	6	Pcs		\$ -		
	3'-0"x 4'-0"	1	Pcs		\$ -		
	2'-0"x 2'-0"	1	Pcs		\$ -		
	Frabricate and install burglar proofing bars with 1/2" solide square bars as per design to fit in the following window openings:						
	4'-0"x 5'-0"	6	Pcs		\$ -		
	3'-0"x 4'-0"	1	Pcs		\$ -		
	2'-0"x 2'-0"	1	Pcs		\$ -		
	Sub-total to Summary				\$ -		
	Total Building structure Works				\$ -		

Bill of Quantities

Item	DESCRIPTION	QTY	UNIT	PRICE (USD)	AMOUNT (USD)		
	FINAL WORKS						
H	Plumbing works						
	<u>Rough Plumbing</u>						
	Allow SUM for plumbing rough works as required	1	L/S		\$ -		
	<u>Plumbing fixtures</u>						
	Provide and install the following plumbing materials at designated locations as per design						
	Kitchen Sink + fuarcet	1	Set		\$ -		
	Cammode	2	Sets		\$ -		
	Face Basin	2	Sets		\$ -		
	Tissue Holder	2	Pcs		\$ -		
	Towel rail(Kitchen and Bathroom)	3	Pcs		\$ -		
	Shower stand complete	2	Sets		\$ -		
	Sub total to summary				\$ -		
I	Electrical Work						
	<u>Rough work</u>						
	Allow SUM rough work and wiring the entire building	1	L/S		\$ -		
	<u>Fixtures</u>						
	Provide and install the following electrical fixtures at designated locations						
	Lamp holder	12	Pcs		\$ -		
	Energy Lamp(45 watts)	12	Pcs		\$ -		
	Single pole switches	12	Pcs		\$ -		
	220 voltage outlet receptacle	10	Pcs		\$ -		
	8 Breaker panel	1	Pcs		\$ -		
	Sub total to Summary				\$ -		
J	Screeding						
	<u>Trowel finished cement-sand screed;</u>						
	Ordinary portland cement	18	Bags	\$ -	\$ -		
	Beach Sand	12	CY	\$ -	\$ -		
	Sub total to Summary				\$ -		
K	Tilling						
	<u>Floor tiles</u>						
	Provide and install 12" x 12" ceramic floor tiles	118	Carton		\$ -		
	Ordinary portland cement	50	Bags	\$ -	\$ -		
	White cement	2	Bags		\$ -		
	Beach Sand	10	CY	\$ -	\$ -		
	<u>Wall tiles</u>						
	Provide and install 9" x 12" ceramic wall tiles	30	Carton		\$ -		
	Ordinary portland cement	15	Bags	\$ -	\$ -		
	White cement	2	Bags		\$ -		
	Beach sand	3	CY	\$ -	\$ -		
	Sub total to Summary				\$ -		
L	Painting						
	Prepare and apply 1 coat of white wash on wall surfaces	2	Bags		\$ -		
	Prepare and apply two coats of emulsion paint on all wall surfaces	14	Bkts		\$ -		
	Prepare and apply two coats of oil paint on metal, wood and plinths	6	Gals		\$ -		
	Paint roller	12	Pcs		\$ -		
	Paint brushes	4	Pcs		\$ -		
	Sand paper(Assorted Grades)	1	Box		\$ -		
	Sub total to Summary				\$ -		
	Total of Final Works				\$ -		
	TOTAL CONSTRUCTION COST				\$ -		
	ITC is exempt of VAT and of any other duties						
Prices quoted above should be inclusive of all the costs associated with the provision of the required construction works as detailed in the TOR.							
ITC will not be responsible for any other costs associated with provision of deliverables, therefore all personnel, travel, allowances, hire, fees and any other related costs shall be all inclusive, i.e. be included in the above rates.							
	I confirm that the above rates are all inclusive and remain valid for 180 days after tender closure			Signature Date			