



WINDOW SCHEDULE	
W1	= 1500 x 1200
W2	= 1200 x 1000

DOOR SCHEDULE	
D1	= 1500 x 2100
D2	= 850 x 2100



Roof:  
 Roof Pitch 27°  
 150 x 50mm Rafters  
 100 x 50mm Ties & struts  
 100 x 40mm sw wall plates  
 75 x 50mm sw purlins  
 225 x 25mm sw fascia board  
 Galvanised steel roofing sheets

Foundation:  
 250mm thick gravel  
 50mm thick well compacted sand  
 polythene sheet as damp proof membran  
 BRC mesh ref S193  
 100mm thick slab  
 30mm screed finish



AFO - Zimbabwe Office  
Harare, Zimbabwe

Project:

**INFRASTRUCTURE SUPPORT TO GLOBAL FUND FOR TREATMENT OF AIDS, TUBERCULOSIS AND MALARIA (GFATM) - ROUND 8 PHASE II**  
 Construction of New Pharmacy Storage Block at Mufudziwakanaka Rural Health Clinic, Mashonaland East-Zimbabwe

DRAWING TITLE

**FLOOR PLAN, ELEVATIONS & SECTION**

CONTRACT No:	SCALE: 1:100 @ A3
DESIGNED BY: UNOPS	REVISION No:
DRAWN BY: UNOPS	DATE: 12-08-13
APPROVED FOR IMPLEMENTATION:	CAD DWG No: ARC MRHC-UNOPS ZW 01